

## Camp Pendleton Marine Base

### ■ Location:

Oceanside, CA

### ■ Pipe Used:

18-inch HDPE DR 11  
12-inch HDPE DR 9

### ■ Quantity of Pipe:

4,000 feet

### ■ Type of Project:

Force sewer main installed using horizontal directional drilling under the Santa Margarita River

### ■ Duration of Project and Pipe Installation:

2008- 3 months

