

## U.S. 75 Water Line Project

### ■ Location:

Allen, TX

### ■ Pipe Used:

18-inch HDPE DR 11 Blue Stripe

### ■ Quantity of Pipe:

7,760 feet of 18-inch HDPE DR 11 Blue Stripe

### ■ Type of Project:

Water line replacement job using slip line installation method.

### ■ Duration of Project and Pipe Installation:

March 2011- July 2011

### ■ Additional Comments:

18-inch HDPE pipe was pulled into existing 24-inch ductile iron pipe. Slip line installation saved 20+ businesses from disruption or inconvenience during the construction.

Engineer: Birkhoff, Hendricks and Carter.

Distributor: Fortiline Pipe and Supply.

Contractor: Pittard Construction

